Enerco Construction Heaters



ENERCO CONSTRUCTION PORTABLE HEATERS

Designed for the worker, HeatStar portable heaters keeps your team comfortable at the job-site, allowing to work longer and more effectively in unseasonable weather to maintain your project deadlines. Convection Heaters

- Made in China
- Piezo Push Button Igniter
- Thermocouple Operated Gas Valve
- No Electricity Required
- Telescoping Chamber
- Clean Burning, Quiet, Odorless
- Insta-lock Chamber Assembly
- Standing Pilot for Insured Safety
- 20 ' 3/8" I.D. Hose w/ Regulator and POL (HS80CV)
- 20' 1/4" I.D. Hose w/ Regulator and POL (HS200CV)
- POL / Excess Flow Check Valve



HS80CV

Model #	Gas Type	Operation	Btu's	Description	Width	Depth	Height
HS80CV	LP	Standing Pilot	30,000 - 80,000	Convection Industrial Construction Portable Heater w/ 20' Hose & Regulator	18.25"	17.75"	16"
HS100CVNG	NG	Standing Pilot	50,000 - 100,000	Convection Industrial Construction Portable Heater	18''	18''	19"
HS200CV	LP	Standing Pilot		Convection Industrial Construction Portable Heater w/ 20' Hose & Regulator	18''	18''	19"

ENERCO DIRECT-FIRED FORCED AIR PORTABLE HEATERS

- Made in China (excluded HS125FAV made U.S.A)
- Flame Safety Control
- Electricity Necessary
- Adjustable Height Control (HS85FAV,HS125FAV,HS170FAVT)
- Built-In Thermostat (HS170FAVT, HS400FAVT)
- 20 ' 1/4" I.D. Hose w/ Regulator and POL (HS35FA, HS400FAVT)
- 20 ' 3/8" I.D. Hose w/ Regulator and POL (HS85FAV,HS125FAV,HS170FAVT)
- POL Excess Flow Check Valve



HS35FA

Model #	Gas Type	Operation	Btu's	Description	Width	Depth	Height
HS35FA	LP	Piezo Ignition	35,000	Forced Air Construction Heater w/ 20' Hose & Regulator	20-3/4"	9-3/4"	12-3/4"
HS85FAV	LP	Continuous Ignition	50,000 - 85,000	Forced Air Construction Heater w/ 20' Hose & Regulator	18-1/4"	11-1/2"	14"
HS125FAV	LP	Continuous Ignition	75,000 - 125,000	Forced Air Construction Heater w/ 20' Hose & Regulator	21-1/4"	11-3/4"	15-3/4"
HS170FAVT	LP	Thermostatic	125,000 - 170,000	Forced Air Construction Heater w/20' Hose & Regulator and Built-In Thermostat	26-1/2"	11-1/2"	16-1/2"
HS170NG	NG	Thermostatic	150,000	Forced Air Construction Heater w/20' Hose & Regulator and Built-In Thermostat	26-1/2"	11-3/4"	16-1/4"
HS400FAVT	LP	Thermostatic	250,000 - 400,000	Forced Air Construction Heater w/20' Hose & Regulator and Built-In Thermostat	38-1/2"	14-3/4"	22-1/4"

rmî

Enerco Construction Heaters



ENERCO RADIANT PORTABLE HEATERS

- Made in China
- Piezo Push Button Ignition
- Thermocouple Operated Gas Valve
- No Electricity Required
- Clean Burning, Quiet, Odorless
- Tip-Over Switch, Safety Shut-Off
- POL Connection w/ 20' Hose Included (HS35LP,HS125LP)



HS35LP



HS125LP

Model #	Gas Type	Operation	Btu's	Description	Width	Depth	Height
HS35LP	LP	Piezo Ignition	35,000	Radiant Portable Construction Heater w/ 20' Hose and Regulator	10.24"	12.4"	34.25"
HS125LP	LP	Piezo Ignition	125,000	Radiant Portable Construction Heater w/ 20' Hose and Regulator	16.14"	16.14"	35.04"
HS125NG	NG	Piezo Ignition	125,000	Radiant Portable Construction Heater w/ Regulator Only	16.14"	16.14"	35.04"

ENERCO NOMAD TENT AND CONSTRUCTION HEATERS

- Made in U.S.A.
- Spark Ignition, Thermostat w/ 20' Cord, 15' Hose and Regulator
- Quiet Operation
- Multi-Rate Heat Setting
- Easy Reset High Limit Switch, Choose Rate and Fuel w/ Flip of a Switch
- Flexible Diffuser Connector System

ENERCO NOMAD VENTING & ACCESSORIES

Model #	Model Series	Description
F109105	HS115SF, HS115TC	12" Diffuser Kit
F109106*	HS115SF, HS115TC	12" Duct Adapter
F109107	HS115SF, HS115TC	12" x 30" Short Duct
F109108	HS115SF, HS115TC	12" x 10' Long Duct
F109115	HS190SF,HS250SF,HS190TC,HS250TC	16" Diffuser Kit
F109116	HS190SF,HS250SF,HS190TC,HS250TC	16" Duct Adapter
F109117	HS190SF,HS250SF,HS190TC,HS250TC	16" x 30" Short Duct
F109118	HS190SF,HS250SF,HS190TC,HS250TC	16" x 10' Long Duct
F109119	HS190SF,HS250SF,HS190TC,HS250TC	Storage Box
F273737	All Models	Dual LP Tank Hook Up Kit

* Optional Accessory - Required for Vented Operation





HS115

HS250





F109118

F273737

Model #	Gas Type	Operation	Btu's	Btu's Description		Depth	Height
HS115SF	LP	Spark Ignition	81,000 - 111,000	Nomad Single Fuel Tent & Construction Heater w/Thermostat and 20' Cord, 15' Hose and Regulator	15"	30"	23.8"
HS190SF	LP	Spark Ignition	127,000 - 190,000	Nomad Single Fuel Tent & Construction Heater w/Thermostat and 20' Cord, 15' Hose and Regulator	20.3"	35.8"	34.8"
HS250SF	LP	Spark Ignition	181,000 - 249,000	Nomad Single Fuel Tent & Construction Heater w/Thermostat and 20' Cord, 15' Hose and Regulator	20.3"	35.8"	34.8"
HS115TC	LP/NG Dual Fuel	Spark Ignition	81-111,000 LP / Nomad Dual Fuel Tent & Construction Heater w/Thermostat, 77,000-108,000 NG 20' Cord, 15' Hose and Regulator		15"	30"	23.8"
HS190TC	LP/NG Dual Fuel	Spark Ignition	ition 127-190,000 LP/ Nomad Dual Fuel Tent & Construction Heater w/Thermostat, 129-184,000 NG 20' Cord, 15' Hose and Regulator		20.3"	35.8"	34.8"
HS250TC	LP/NG Dual Fuel	Spark Ignition	181-249,000 LP / 172-249,000 NG	Nomad Dual Fuel Tent & Construction Heater w/Thermostat, 20' Cord, 15' Hose and Regulator	20.3"	35.8"	34.8"